

Kansas Corporation Commission

District Plugging Report

(Diskin-Verl)

API Well Number: 15-037-01751-0000
Spot: NW/SW/NW Sec 14 Twp 29 S Rng 21
Feet from 3618 N/S Line of Section
5194 E/W Line of Section
GPS: Lat: 37.524636 Long: 95.088231 Date: 4/4/13
Lease Name: DISKIN FARMS PROJECT (Pasture) Well #: VERL 01
County: Crawford Total Vertical Depth: 220 feet

Operator License No: 101
Op Name: KANSAS CORPORATION COMMISSION
Address 1: 130 S MARKET
Address 2:
City: WICHITA
State: KS Zip Code: 67202
String: DRIVE - Drive Pipe Size: 6.000

Well Type: OG - Oil & Gas (EOL)
UIC Docket No.:
Date/Time to Plug: 10/16/13
Plug Co License No.: 33749
Plug Co. Name: KWS
Proposal Rcvd from: MIKE KEPLEY
Company Name: KWS Phone: (620) 431-9212

Proposed Plugging Report: CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.

Plugging Proposal Received By: TONY ANDERSON
Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 10/16/13
KCC Agent: TONY ANDERSON

Actual Plugging Report table with columns: Perfs, Top, Bottom, Thru. Includes text: DUG OUT WELL AND CUT OFF. FOUND 2" PIPE WITH 1/2" STEEL PIPE IN IT, HAD TO FISH IT OUT. WASHED DOWN OUTSIDE TO 220' AND GOT THRU RAG PACKER. PUMPED 52 SACKS OF CEMENT. THE LOCATION WAS THEN RESTORED.

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 04 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONTRACT#11782; CONTROL#20140002-009;GPS BY TOM,TONY
NAD83

Plugged Thru: TBG - Tubing
Plugged Due to Compliance Issue: Yes No

District: 03
Tony Anderson (Technician)
Form: District Plugging Report