

To: 1070030
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

10-9

API NUMBER 15-007-22,437 -00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA Inc.
Name & Address 400 S. Main
Pratt, KS 67124

SE SE NW, SEC. 22, T 33 S, R 14 W X
3290 feet from S section line
2970 feet from E section line

Lease Name Harbaugh B Well # 1
County Barber 168.03
Well Total Depth 5170 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1064

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9:15 a.m. Day: 9 Month: 10 Year: 19 97

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 5167' w/385 sx cement, PB4686', Perfs at 4644-86'

1st plug sand back to 4595' and dump 5 sx cement on top of sand through bailer,

2nd plug run tubing to 1115', spot 50 sx cement at 1115',

3rd plug spot 50 sx cement at 500',

4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

RECEIVED
OCT 16 1997
10-16-97
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 9 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set wiper plug at 4600' with 125 gallons sand to 4550',

dump 5 sx cement on top,

2nd plug ran tubing to 1115', loaded hole with gel, and spotted 50 sx cement at 1115',

3rd plug spotted 50 sx cement at 500',

4th plug spotted 10 sx cement at 40'.

Good circulation throughout job.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2650' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / observe this plugging.

DATE OCT 23 1997

Signed [Signature]
(TECHNICIAN)

INV. NO. 49275