

To: 041181  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-22,503 - 0000  
NW NE SE, SEC. 36, T 33 S, R 14 W/E  
2310 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT 6-16  
Operator License # 5506

Lease Name Roth Well # 3

Operator: Woolsey Petroleum Corporation  
Name & Address 107 N. Market, Ste. 600  
Wichita, KS 67202-1807

County Barber  
Well Total Depth 5390 175.17 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 1:40 p.m. Day: 16 Month: 6 Year: 19 96

Plugging proposal received from Joe Livingston

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

was: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 600' with 50 sx cement, 2nd plug at 250' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 p.m. Day: 16 Month: 6 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,

2nd plug at 250' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 18 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied.

6-18-96  
CONSERVATION DIVISION

(If additional description is necessary, use BACK WICHITA form.)

INVOICED

(did not) observe this plugging.

DATE 6-25-96

INV. NO. 45878  
6-16

Signed Stephen J. Pfeifer  
(TECHNICIAN)

\*CC USE\*

EFFECTIVE DATE: 4-28-96  
DISTRICT # 1  
SGA? Yes  No

State of Kansas  
NOTICE OF INTENTION TO DRILL

007-22,503-0000

Must be approved by the K.C.C. five (5) days prior to commencing well.

Spot East  
NW NE SE Sec 36 Twp 33 S, Rg 14 XX West

Expected Spud Date: MAY 5TH 1996  
month day year

OPERATOR: License # 5506  
Name: WOOLSEY PETROLEUM CORPORATION  
Address: 107 NORTH MARKET, SUITE 600  
City/State/Zip: WICHITA, KANSAS 67202-1807  
Contact Person: DEBRA K. CLINGAN  
Phone: (316) 267-4379

CONTRACTOR: License #: 5929  
Name: DUKE DRILLING CO, INC.

Well Drilled For: Well Class: Type Equipment:  
... Oil ... Enh Rec  Infield  Mud Rotary  
 Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
... Other  
If OWWO: old well information as follows:  
Operator: n/a  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore?  yes  no  
If yes, true vertical depth:  
Bottom Hole Location:

Exp. 10/23/96  
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

2310' FSL ..... feet from South / North line of Section  
 990' FEL ..... feet from East / West line of Section  
IS SECTION REGULAR  XX IRREGULAR?  
(NOTE: Locate well on the Section Plat on Reverse Side)  
County: BARBER  
Lease Name: ROTH Well #: 3  
Field Name: AETNA  
Is this a Prorated/Spaced Field?  yes  no  
Target Formation(s): MISSISSIPPIAN  
Nearest lease or unit boundary: 990'  
Ground Surface Elevation: 1771' feet MSL  
Water well within one-quarter mile:  yes  no  
Public water supply well within one mile:  yes  no  
Depth to bottom of fresh water: 140'  
Depth to bottom of usable water: 180'  
Surface Pipe by Alternate:  1  2  
Length of Surface Pipe Planned to be set: 200'  
Length of Conductor pipe required: n/a  
Projected Total Depth: 5275'  
Formation at Total Depth: ARBUCKLE  
Water Source for Drilling Operations:  
 well  farm pond  other

Will Cores Be Taken?:  yes  no  
If yes, proposed zone:

200' Alt. I Req.  
RECEIVED RECEIVED  
KANSAS CORPORATION COMMISSION

AFFIDAVIT

Pusher JCC Livingston  
SPUD DATE 5-20-96 INIT. R.C.  
LENGTH SURFACE PLANNED 200'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 2 1/2" @ 25' CONDUCTOR  
ANHYDRITE T- B- ELEVATION  
FD 5 5/8" FORMATION  
RAH PIPE @ SX DV TOOL SX ALT II DONE Y N  
Arbuckle Plug @          Ft. W/ SX  
Jug./Council @          Ft. W/ SX  
Anhydrite Base @ 600 Ft. W/ 50 SX  
         1/2 Base Anyh. @          Ft. W/ SX  
         1/2, 1/2 Plug @          Ft. W/ SX  
Bottom Surface @          Ft. W/ SX  
         40' Plug @          Ft. W/ SX  
RAT HOLE CIRG/W 1 SX MOUSE HOLE W/ 1 SX  
WATER WELL          SX (Irr. Well) Pond           
Hauling           
TECHNICIAN          DATE           
TYPE OF CEMENT           
STARTING TIME 1:11 (AM/PM) DATE 5/16/96  
COMPLETION TIME 2:30 (AM/PM) DATE 6/6/96  
CEMENT COMPANY         

Spud 6-19-96

JUN 18 1996  
6-18-96

CONSERVATION DIVISION  
WICHITA, KS