

To: *

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-21000-0000

NWSWNE Sec/Twp/Rge 16 - 26S - 21E

3818 feet from south section line

1976 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: State of Kansas

Name & _____

Address _____

AB oil well Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road Chanute, KS 66720

Company to plug at: Hour: _____ Day: 23 Month: 11 2009

Plugging proposal received from: Mike Kepley

Company Name: Kepley Well Service, LLC Phone: 620-431-9212

Were: Clean out and prepare well for plugging and circulate cement to surface.

Plugging Proposal Received by: Ryan M. Duling

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXX

Operations Completed: Hour: _____ Day: 23 Month: 11 2009

Actual Plugging Report: Dug down beside the 2.875" casing with a backhoe approximately 4' and found cement around the casing. Ran 1" pipe inside the 2.875" casing to 660'. Washed 1" pipe down inside of 2.875" casing to 715'. Circulated cement through 1" pipe inside 2.875" casing from 715' to surface.

Pulled 350' of 1" pipe. Circulated cement through 1" pipe from 350' to surface. Pulled rest of 1" pipe.

Squeezed well with cement and shut in at 350 psi. A total of 28 sacks of portland cement was used to plug this well. The well was cut off below surface and the location was restored.

Remarks: Contract #12391 Control #20100001-067
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:


TECHNICIAN

RECEIVED

JAN 30 2012

KCC WICHITA