

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22229-00-01  
Spot: NWNESENW Sec/Twnshp/Rge: 22-26S-7E  
3641 feet from S Section Line, 3017 feet from E Section Line  
Lease Name: SIMON Well #: 2A  
County: BUTLER Total Vertical Depth: 2810 feet

Operator License No.: 34569  
Op Name: SONOMA RESOURCES LLC  
Address: PO BOX 384  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2810		100 SX
SURF	8.625	202		130 SX

Well Type: EOR UIC Docket No: E21904.2 Date/Time to Plug: 01/09/2014 8:00 AM  
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC  
Proposal Rcvd. from: DAN FLOWERS Company: SONOMA RESOURCES LLC Phone: (316) 208-7590

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/09/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2329', CONSOLIDATED OIL WELL ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 3% CC, 1/4# POLY FLAKES & DISPLACED IN CASING. WAITED 2 - HOURS, TAGGED CEMENT @ 1967'. RIH ON WIRELINE, SHOT SQUEEZE HOLES 250'-251' (4 HOLES). RIH W/TBG @ 246', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 105 SXS 60/40 POZMIX 35 GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 1-9-2014. CONSOLIDATED CEMENT TICKET #43202.

Perfs:

Top	Bot	Thru	Comments
2742	2774	CSG	

Remarks: FAILED MIT

Plugged through:

District: 02

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

Duane Krueger  
02/17/14 (TECHNICIAN)  
cc to WCC 02/17/14