

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20399-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 6-15S-14W
4205 feet from S Section Line, 1974 feet from E Section Line
Lease Name: MUDD Well #: 1
County: RUSSELL Total Vertical Depth: 3178 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3176		225 sx
SURF	8.625	756		400sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2013 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.
Perforations: 1425', 725' and 275'.
Control # 20140028001
Dig Safe # 13494833

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2013 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

12/09/13- Ran bailer in and got to 2640'. Ran tubing in and got to 2450'. Hooked up to tubing and pumped down washing bottom clean. Ran tubing down to 2946' and had a hard bottom. Called in and decided to plug the well there. Pumped 140 sx cement w/150 # hulls. POOH.
10/10/13- Perforated at 1425', 725' and 275'. Ran tubing to 1450' and pumped 165 sx cement w/300 # hulls. Pulled tubing to 300' and pumped 30 sx cement. Cement circulated. POOH. Hooked to casing and pumped 65 sx cement. Cement circulated out braden head. Shut in and pressured to 300 psi.

GPS: 38.78107 -098.91761

Perfs:

Remarks: QUALITY WELL SERVICE TICKET # 6079 MUDD FEE FUND PROJECT CONTROL # 20140028001

Plugged through: TBG

District: 04

Signed

R. Dink

(TECHNICIAN)

CM

Form CP-2/3

JAN 02 2014

KCC WICHITA

JAN 09 2014

RECEIVED