

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20998-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 6-15S-14W
1763 feet from S Section Line, 2290 feet from E Section Line
Lease Name: MUDD Well #: 3
County: RUSSELL Total Vertical Depth: 3174 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3173		100 sx
SURF	8.625	757		330 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/26/2013 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls and 8 sx gel.
15 joints of 2 3/8" tubing dropped in well.
Control # 20140028002
Dig Safe # 13494833

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/26/2013 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2800' and pumped 4 sx gel followed by 50 sx cement. Pulled tubing to 1450' and pumped 175 sx cement w/250 # hulls. Pulled tubing to 715' and pumped 145 sx cement w/300 # hulls. Cement circulated. POOH. Hooked to casing and pumped 35 sx cement. Circulated cement out the braden head.
11/27/2013- Topped off w/10 sx cement.

GPS: 38.77436 -098.91904

Remarks: QUALITY WELL SERVICE TICKET # 6077 MUDD FEE FUND PROJECT CONTROL # 20140028002

Plugged through: TBG

District: 04

Signed

RAO.K

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

JAN 09 2014

RECEIVED

JAN 02 2014