

1 080569

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,580 -0000

SW NE NW, SEC. 5, T. 35 S, R. 11 (W) X
4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name Sippel Well # 1

Operator: McGinness Oil Co.

County Barber 154.70

Name & Address 1026 Union Center,

Well Total Depth 4760 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:45 p.m. Day: 25 Month: 11 Year: 19 86

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4759' PBSD 4725' Perfs at 4728 1/2-46 1/2' Elevation 1331'

1st plug sand back to 4660' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 25 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix by B.J. Titan. Recovered 3600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
IN div. of STATE CORPORATION COMMISSION

Signed J. A. [Signature] (TECHNICIAN)

DATE 12-3-86 DEC 2 1986 12-2-86

INV. NO. 15458 CONSERVATION DIVISION Wichita, Kansas