

To: 1 040664 5-19  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-20,361-0000 140  
C NW NW, SEC. 5, T. 35 S, R. 11 W/E R  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006  
Operator: Molz Oil Company  
Name & Address: RR 2, Box 34  
Kiowa, KS 67070

Lease Name Bond Goldman Well # 1  
County Barber  
Well Total Depth 5258 170.88 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 247

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 19 Month: 5 Year: 19 92

Plugging proposal received from Ray Wills  
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5258', Perfs at 4748-51, 4763-69, 4784-90'.

1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10  
sx gel, 100 lbs: hulls, release 10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 19 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 4 sx cement on top of sand  
bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Maximum pressure 350 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3700' of 4 1/2" casing  
(if additional description is necessary, use BACK of this form.) 5-27-92

**INVOICED**  
I (or my authorized representative) observe this plugging.

DATE 6-3-92  
INV. NO. 35368

Signed Stephen J. Pfeifer (TECHNICIAN)  
STATE CORPORATION COMMISSION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1992  
FORM CP-2/3  
Rev. 01-84