

8-8-88 15-007-10343-0000

To: 1 030966
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 6/17/56
SW NE NW, SEC. 26, T 33 S, R 14 W/E
4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5428
Operator: Graves Drilling Company, Inc.
Name & Address 151 North Main, Suite 850
Wichita, KS 67202

Lease Name George Well # 2
County Barber 159.48
Well Total Depth 4907 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 8 Month: 8 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4905' PBSD 4880' Perfs at 4852-61'

1st plug set CIBP at 4800' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 25 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, 100 sx cement,

3rd plug spot 25 sx cement at 900' and 310',

4th plug pump 25 sx cement at 40-0.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:45 p.m. Day: 8 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4800' with 2 sx cement on top,

2nd plug ran tubing to 750' and fill 5 1/2" pipe with heavy mud and pump 75 sx cement, filling 5 1/2" to 0',

3rd plug pumped 100 sx cement down 8 5/8".

Maximum pressure 600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. No casing recovery.

(If additional description is necessary, use BACK of this report)

Wichita, Kansas

INVOICED (Note) observe this plugging.

DATE 8-11-88

INV. NO. 21836

Signed Steve Dumont (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION AUG 10 1988 8-10-88 CONSERVATION DIVISION

BJ-TITAN SERVICES

P.O. BOX 4442 HOUSTON, TX 77210

CEMENTING LOG

STAGE NO.

15-007-10343-0000

Date 9/3/88 District Med. 6000 Ticket No. 422279
 Company BRAY, DAIG, CO. INC. Rig CLARK W.S.
 Lease GEORGE Well No. 2
 County EARL State KANSAS
 Location 26-33s-14W Field _____

CEMENT DATA:
 Spacer Type: 3 Bbls. FRESH WATER
 Amt. _____ Sks Yield _____ ft³/sk Density _____ PPG

CASING DATA: PTA Squeeze
 Surface Intermediate Production Liner
 Size 5/2" Type _____ Weight _____ Collar _____

LEAD: Pump Time _____ hrs. Type _____
 Excess _____

Amt. _____ Sks Yield _____ ft³/sk Density _____ PPG

TAIL: Pump Time _____ hrs. Type 60/40 107
6% Gel Excess _____

Amt. _____ Sks Yield 1.56 ft³/sk Density 13.9 PPG

WATER: Lead _____ gals/sk Tail 7.9 gals/sk Total _____ Bbls.

Casing Depths: Top _____ Bottom _____
3/8" 61-230' BRAY PILL ST
5/2" 61-4905 AT 4000'

Pump Trucks Used C7-40 S. KOKIAN
 Bulk Equip. T-35 B. CROSBY

Drill Pipe: Size _____ Weight _____ Collars _____
 Open Hole: Size _____ T.D. _____ ft. P.B. to _____ ft.

Float Equip: Manufacturer _____

CAPACITY FACTORS:
 Casing: Bbls/Lin. ft. .0244 Lin. ft./Bbl. 41
 Open Holes: Bbls/Lin. ft. _____ Lin. ft./Bbl. _____
 Drill Pipe: Bbls/Lin. ft. _____ Lin. ft./Bbl. _____
 Annulus: Bbls/Lin. ft. _____ Lin. ft./Bbl. _____
706. Bbls/Lin. ft. .0039 Lin. ft./Bbl. 253
 Perforations: From 4352 ft. to 4361 ft. Amt. _____

Shoe: Type _____ Depth _____
 Float: Type _____ Depth _____
 Centralizers: Quantity _____ Plugs Top _____ Btm. _____
 Stage Collars _____
 Special Equip. _____
 Disp. Fluid Type _____ Amt. _____ Bbls. Weight _____ PPG
 Mud Type _____ Weight _____ PPG

COMPANY REPRESENTATIVE ROB MILLER

CEMENTER KEVIN BUNCALOT

TIME	PRESSURES PSI		FLUID PUMPED DATA			REMARKS
	DRILL PIPE CASING	ANNULUS	TOTAL FLUID	Pumped Per Time Period	RATE Bbls/Min.	
10:00						ON LOCATION, HOW SATISFY MTR. R26 LT
10:45	300		2	3		TUMP FRESH WATER
	400		21	18		MIX 65% CEMENT VIA TUBING CALIBRATE TO SURFACE
	300		49	23		TUMP 100% CEMENT VIA ANNULUS
12:45			52	3		PULL TUBING TO TOP OF ST 5/2" WITH 100% CEMENT
						MAY 600#
						SI 100#

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1988
 8-10-88
 CONSERVATION DIVISION
 Wichita, Kansas

FINAL DISP. PRESS: _____ PSI BUMP PLUG TO _____ PSI BLEEDBACK _____ BBLs. THANK YOU