

1 080064

5-9

left

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,315-0000

C SE SW, SEC. 27, T 33 S, R 14 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Wheat Well # A-1

Operator: TXO Production Corporation
Name & Address: 1660 Lincoln Center Bldg., #1800
Denver, CO 80264

County Barber 159.15
Well Total Depth 4897 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 410

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address 2759 S. Broadway, Wichita, KS 67216

Company to plug at: Hour: 4 p.m. Day: 9 Month: 5 Year: 19 90

Plugging proposal received from Butch Steinert

(company name) Eagle Drilling, Inc. (phone) 316-945-9935

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 800' with 100 sx cement, 2nd plug at 440' with 80 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6 p.m. Day: 9 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 800' with 100 sx cement,

2nd plug at 440' with 80 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED observed this plugging.

DATE MAY 22 1990
INV. NO. 2821
CONSERVATION DIVISION
Wichita, Kansas

Signed Mike Spain (TECHNICIAN)

5-9

EFFECTIVE DATE: 4/30/90 State of Kansas
NOTICE OF INTENTION TO DRILL

007-22,315-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 5 1 1990
month day year

C. SE. SW. Sec 27. Twp 33. S, Rg 14. East
West

OPERATOR: License # 5171 ✓
Name: TXO Production Corp.
Address: 1660 Lincoln Center Building #1800
City/State/Zip: Denver, CO 80264
Contact Person: Cory West
Phone: (303) 861-4246

660' feet from South line of Section
3300 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5380 ✓
Name: Eagle Drilling, Inc.

County: Barber
Lease Name: Wheat Well #: A-1
Field Name: ActNA

Well Drilled For: Well Class: Type Equipment:
... Oil ... Inj ... Infield X Mud Rotary
X Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWD ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

* Is this a Prorated Field? ... yes X no ✓
Target Formation(s): Viola
Nearest lease or unit boundary: 660
Ground Surface Elevation: unknown feet MSL
Domestic well within 330 feet: ... yes X no
Municipal well within one mile: ... yes X no
Depth to bottom of fresh water: 250
Depth to bottom of usable water: 250
Surface Pipe by Alternate: X 1 ... 2
Length of Surface Pipe Planned to be set: 350
Length of Conductor pipe required: none
Projected Total Depth: 5000
Formation at Total Depth: Viola
Water Source for Drilling Operations:
... well ... farm pond X other

If OAWD: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

DWR Permit #: _____
Will Cores Be Taken? ... yes ... no
If yes, proposed zone: _____


Directional, Deviated or Horizontal wellbore? ... yes ... no
If yes, total depth location: _____

* This Field is prorated for Mississippian Gas; 160 A Spacing;
Located in one of the AFFIDAVIT 4 ten-acre spots
Exp. 10/25/90 200' Alt. I Re

PUSHER Butch
TD 4897 FORMATION M.S.S.
SURFACE PIPE 8 1/2 @ 410
Rat hole 7 1/2 @ 1100
ANHYDRITE _____ ELEVATION _____
STARTING TIME & DATE 4:00 P 5-9
COMPLETION TIME & DATE 6:00 AM
1st PLUG @ 800 FT. W/ 100 SX
2nd PLUG @ 440 FT. W/ 80 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ _____ FT. W/ _____ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ _____ SX
CEMENT COMPANY B.J. T. Law
TECHNICIAN M.S.
TYPE OF CEMENT 60/40 60% 1/4 lb

Spud 5-1-90

RECEIVED
STATE CORPORATION COMMISSION



- REMEMBER TO:
- file Drill Pit Application (form CDP-1) with Intent to Drill;
 - file Completion form ACO-1 within 120 days of spud date;
 - file acreage attribution plat according to field prorated orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.

cut