

To: 1 070029
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

10-9 API NUMBER 15- 007-20,661-0001

TECHNICIAN'S PLUGGING REPORT

SW SE NE, SEC. 28, T 33 S, R 14 W/E
2970 feet from S section line
990 feet from E section line

Operator License / 5447

Lease Name Harbaugh H Well # 3

Operator: OXY USA Inc.

County Barber 157.95

Name & Address 400 S. Main

Well Total Depth 4860 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 12:45 p.m. Day: 9 Month: 10 Year: 19 97

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

work: 5 1/2" at 4856' w/195 sx cement, Perfs at 4605-30, 4708-12'

1st plug sand back to 4540' and dump .5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 p.m. Day: 9 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4540' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

RECEIVED STATE CORPORATION COMMISSION

OCT 16 1997 10-16-97

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3100' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE OCT 23 1997

INV. NO. 49274

Signed [Signature] (TECHNICIAN)