

To: 1040649 f-21
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-007-01142-0000 182
API NUMBER 15-DRILL COMPLETION DATE 5/6/58

SE NW, SEC. 28, T. 33 S, R 14 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3048
Operator: Bristol Resources Corp.
Name & Address 6655 S. Lewis, Ste. 200
Tulsa, OK 74136

Lease Name Davis Ranch Well # A-1
County Barber
Well Total Depth 4640 150.80 feet
Conductor Pipe: Size 12 1/2 feet 63
Surface Casing: Size 8 5/8 feet 800
Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____
Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 9:45 a.m. Day: 21 Month: 4 Year: 19 92
Plugging proposal received from Bruce Wagner
(company name) Pratt Well Service (phone) 316-672-2531
were: 4 1/2" at 4639', PBSD 4639', Perfs at 4586-4626'

1st plug set CIBP at 50' above perfs,
2nd plug pump 50 sx cement at 830',
3rd plug pump 40 sx cement at 400',
4th plug pump 10 sx cement at 60'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11 a.m. Day: 21 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 2 3/8" tubing shot off at 2975'. 1587' of 2 3/8" tubing left in hole.
1st plug set CIBP at 2768' and dumped 2 sx cement on top of CIBP through bailer,
Ran tubing in to 830'. Loaded hole with gel (mixed 20 sx of gel).
2nd plug at 830' with 50 sx cement,
3rd plug at 400' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2517' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED
DATE MAY 04 1992
INV. NO. 35113

Signed Stephen J. Pfeiffer
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
4-24-92
APR 24 1992
CONSERVATION DIVISION
Wichita, Kansas