

TO:

API NUMBER 15-001-03597-0000

STATE CORPORATION COMMISSION

SE, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 1011 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 580 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BURTISS WELL # 5

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 10

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE	FEET
----------------------	------

[illegible]

SURFACE CASING: SIZE 8" FEET N/A

ADDRESS

ABANDONED OIL WELL	X GAS WELL	INPUT WELL	SWD WELL	D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS ROUTE 4, BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 10 MONTH: 2 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN

CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 4 1/2" CASING TWICE

AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:15 AM DAY: 10 MONTH: 2 YEAR: 99

ACTUAL PLUGGING REPORT THE 4 1/2" CASING WAS PERFORATED AT 500' AND AT 250'

PIPE WAS RAN INTO THE 4 1/2" CASING TO 775'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM BOTH THE 4 1/2" AND 8" AT SURFACE. THE 1" PIPE WAS REMOVED.

SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 146 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

Control # 19990001-005