

TO:

API NUMBER 15-001-03548-0000

STATE CORPORATION COMMISSION *2-10* SE, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 1019 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 977 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BURTISS WELL # 7

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 10

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE	FEET
----------------------	------

NAME AND	FEE FUND PLUGGING
ALAN W. BROWN	
BILL J. HARRIS	
CAROL A. HARRIS	
DONALD E. HARRIS	
EUGENE L. HARRIS	
GARY D. HARRIS	
HENRY C. HARRIS	
JAMES R. HARRIS	
KENNETH L. HARRIS	
LARRY D. HARRIS	
MICHAEL J. HARRIS	
NATHAN I. HARRIS	
ROBERT M. HARRIS	
SAMUEL S. HARRIS	
TIMOTHY J. HARRIS	
VICTOR J. HARRIS	
WALTER J. HARRIS	
XAVIER J. HARRIS	
YVES J. HARRIS	
ZACHARY J. HARRIS	

SURFACE CASING: SIZE 8" FEET N/A

ADDRESS

ABANDONED OIL WELL X	GAS WELL	INPUT WELL	SWD WELL	D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS ROUTE 4, BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 12:00PM DAY: 10 MONTH: 2 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN

CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE CASING TWICE

AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL>

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE 51

OPERATIONS COMPLETED: HOUR: 1:45 PM DAY: 10 MONTH: 2 YEAR: 99

ACTUAL PLUGGING REPORT THE 4 1/2" CASING WAS PERFORATED AT 500' AND AT 200'. 1"

PIPE WAS RAN INTO THE 4 1/2" CASING TO 750'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM BOTH THE 4 1/2" AND 8" AT SURFACE. THE 1" PIPE WAS REMOVED.

SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 156 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Rayton R. Little
(TECHNICIAN) FORM CP-2/3

Control # 19990001-007

RECEIVED
CAISAS CORP COMPT
1991 FEB 25
10:5