

3021582

TO:

API NUMBER

15-001-03549-0000

STATE CORPORATION COMMISSION

2-4

SE, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

1065 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

1871 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BORTISS WELL # 27

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 10" FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, ROUTE 4, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 10:00AM DAY: 4 MONTH: 2 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED

IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS

POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 12:30PM DAY: 4 MONTH: 2 YEAR: 99

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 2" CASING TO 735'. CEMENT WAS

PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 2" ANNULUS AT

SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 10" ANNULUS TO

600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 10" AT

SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGES AND DISPLACEMENT WERE FILLED FROM SURFACE.

214 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

Control # 19990001-027

RECEIVED
KANSAS CORP COM
FEB 19 1999