

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-21107-00-01  
Spot: NENWSWSE Sec/Twnshp/Rge: 14-19S-2W  
1182 feet from S Section Line, 2196 feet from E Section Line  
Lease Name: MEYERS B Well #: 7 TWIN  
County: MCPHERSON Total Vertical Depth: 3896 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3511		100 SX
SURF	10.75	214		225 SX

Well Type: SWD UIC Docket No: D23168.0 Date/Time to Plug: 12/12/2013 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ROCH MILLER Company: D S & W WELL SERVICING, INC. Phone: (620) 786-5161

Proposed Plugging Method: Per KCC direction, Hunter Clark w/KCC has advised us to file this CP-1, we are still working on wellbore, but do not know outcome yet of workover/fishing operation.

Plugging Proposal Received By: WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/12/2013 3:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

RAN TUBING TO 3387' SET A 35 SX PLUG 100 LBS HULLS. PERF @ 250' 4 SHOTS.  
RAN TUBING TO 313' CIRC CEMENT. 75 SXS TO SURFACE. PULLED PIPE TOPPED  
OFF WITH 40 SXS. ALL 60/40 4% CEMENT USED.

Perfs:

Top	Bot	Thru	Comments
3512	3896		

Remarks: CHECKED TOP PLUG @ 12/13/13 GOOD

Plugged through: TBG

District: 02

Signed

*[Handwritten Signature]*  
3/04/14

(TECHNICIAN)

cc to KCC 3/04/14

KCC WICHITA

Form CP-2/3

FEB 19 2014

RECEIVED

*[Handwritten mark]*