

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21342-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 34-31S-20W
2045 feet from S Section Line, 2160 feet from E Section Line
Lease/Unit Name: EDMONSTON Well Number: 1-34
County: COMANCHE Total Vertical Depth: 5980 feet

Operator License No.: 31821
Op Name: J-F OIL COMPANY LLC
Address: 1119 TOULON AVE
HAYS, KS 67601

Conductor Pipe: Size 10.75 feet: 244
Surface Casing: Size 8.625 feet: 614
Production: Size feet:
Liner: Size feet:
\$194.35

Well Type: DH UIC Docket No: Date/Time to Plug: 01/17/2003 1:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 975' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 01/17/2003 3:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


8 5/8" CMT AT BOTTOM. BASKET AT 85' & CMT WITH 150 SX CMT ON TOP. 1ST PLUG AT 975' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
JAN 23 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. SET 20" CONDUCTOR AT 81'.

Plugged through: DP

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 1-24-03
VV. NO. 2003061111

[Handwritten mark]
Form SP-203