

8-19

031461

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202  
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- 033-20,937-00-00  
C SW NW, SEC. 19, T 31 S, R 20 W X  
1980 feet from NX section line  
660 feet from WX section line

Operator License / 5038  
Operator: Robinson Oil Company  
Name:  
Address 300 W. Douglas, Ste. 420  
Wichita, KS 67202

Lease Name Ward A Well # 1  
County Comanche 170.37  
Well Total Depth 5242 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 856

Abandoned Oil Well Gas Well Input Well SWD Well D&A X  
Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418  
Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 12 a.m. Day: 19 Month: 8 Year: 19 97

Plugging proposal received from Marvin Petz  
(company name) Allen Drilling Company (phone) 316-793-5681

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1104'  
1st plug at 1170' with 50 sx cement, 2nd plug at 870' with 50 sx cement,  
3rd plug at 40-0' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

RECEIVED  
AS CORP COM  
AUG 20 11:25

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 a.m. Day: 19 Month: 8 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1170' with 50 sx cement,  
2nd plug at 870' with 50 sx cement,  
3rd plug at 40-0' with 10 sx cement,  
4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

DATE AUG 21 1997  
INV. NO. 48839

Signed Steve Durrant  
(TECHNICIAN)