

To: 1:051516
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,814-0000 1-9-92 10 R
NE SW SE SW, SEC. 17, T. 31 S, R. 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444

Operator: Charter Production Company
Name & Address 224 E. Douglas, Suite 400
Wichita, KS 67202

645 feet from S section line
3780 feet from E section line
Lease Name Huck Well # 1-17
County Comanche 208.00
Well Total Depth 6400 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 611

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2 p.m. Day: 9 Month: 1 Year: 19 92

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 6399' w/250 sx cement, PBD 6049', Perfs at 5932-82'

1st plug set CIBP at 5900' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 9 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5900' with 2 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 1992

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2909' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-17-92

Signed Richard W. Lucey
(TECHNICIAN)

INV. NO. 34367
1-9