

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21082-01-00
Spot: NWNENE Sec/Twnshp/Rge: 17-31S-20W
195 feet from N Section Line, 1213 feet from E Section Line
Lease/Unit Name: HUCK Well Number: 1-17H
County: COMANCHE Total Vertical Depth: 5903 feet

Operator License No.: 4782
Op Name: ENSIGN OPERATING CO.
Address: 1225 17TH ST., STE 1900
DENVER, CO 80202

Conductor Pipe: Size 20 feet: 100
Surface Casing: Size 9.625 feet: 1250 WITH 365 SX CMT
Production: Size 7 feet: 6156 WITH 165 SX CMT
Liner: Size feet:

8191.85

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/17/2002 12:30 PM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: JERRY DUNKIN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 6100' WITH 4 SX CMT. 1ST PLUG AT 1280' WITH 75 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/17/2002 2:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

THIS IS A HORIZONTAL WELL. PBTD 5378'. OPEN HOLE. CIBP @ 6100' WITH 4 SX CMT ON TOP WITH BAILER. LOAD HOLE WITH MUD. 1ST PLUG AT 1280' WITH 75 SX CMT THROUGH 2 7/8" TUBING. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 15 SX CMT. GOOD CIRCULATION ON JOB.

RECEIVED
SEP 26 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY DUNKIN WELL SERVICE. RECOVERED 4000' OF 7" CASING.

Plugged through: TBG

District: 01

Signed 
(TECHNICIAN)

INVOICE SEP 18 2002

DATE 927-02

WV. NO 2003060580


Form C-23