

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22118-00-01
Spot: NWSENW Sec/Twnshp/Rge: 6-13S-16W
1650 feet from N Section Line, 1650 feet from W Section Line
Lease Name: WALTERS Well #: 4
County: ELLIS Total Vertical Depth: 3520 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 211 S FRONT ST
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3515		150 SX
SURF	8.625	210		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2014 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEREMY SCHECK Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 483-0395

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.
Scout card shows well as dry hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2014 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report: _____ Perfs: _____

Log tech perforated at 1650', 1180' and 650'.
Express Well Service ran in hole with tubing to 3381'. Quality rigged to tubing and mixed and pumped 13 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1640'. Quality mixed and pumped 160 sx cement w/250 # hulls mixed in to circulate cement up 5 1/2" casing. Pulled tubing. Topped off 5 1/2" casing with 10 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 5 sx cement to pressure with 200 psi and 200 psi shut in pressure.
GPS: 38.95286 -099.14476
3208' FSL 3562' FEL
NW SW SE NW

KCC WICHITA
FEB 26 2014
RECEIVED

Remarks: QUALITY OILWELL CEMENTING TICKET # 7726

Plugged through: TBG

District: 04

Signed  (TECHNICIAN) *CM*

FEB 19 2014

FEB 19 2014