

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20102-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 4-33S-41W
422 feet from S Section Line, 406 feet from E Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 16-1-A
County: MORTON Total Vertical Depth: 5119 feet

Operator License No.: 34832
Op Name: SCOUT ENERGY MANAGEMENT LLC
Address: 14400 MIDWAY RD
DALLAS, TX 75244

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3909		
PROD	4.5	5108	1805	WITH 200 SX CMT
RBP		3909		WITH 25 SX CMT
SURF	8.625	1507		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2014 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: ALAN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 1. MIRSU. UNFLANGE WELL & NU BOP. SPOT 2 3/8 WORK STRING. PU 2 3/8 TUBING & TIH TO 3900. CIRCULATE HOLE W/ MUD & SPOT 25 SACKS OF CEMENT ON TOP OF EXISTING RBP AT 3909. POH W/ TUBING AT 2400 FT. MIX & SPOT 35 SACKS OF CLASS C CEMENT TO COVER TIGHT SPOTS & SPLIT IN CASING AT 2075-2345. POH W/ TUBING.2. ND BOP, UNPACK 4 1/2 CASING & WELD ON 4 1/2 PULL SUB. CUT & PULL FREE PIPE +/- 1600 FT.3. TIH W/ TUBING AT 1537 FT. MIX & SPOT 80 SACKS OF CEMENT. POH W/ TUBING AT 550 FT. MIX & SPOT 60 SACKS CEMENT. POH W/ TUBING & ND BOP & TOP OUT 64-4 W/ 20 SACKS OF CEMENT.4. RDMOSU. CUT & CAP WELL. DIG UP RIG ANCHORS.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2014 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****CASING LEAKS FROM 2203'-2245'** RBP @ 3909'. SPOT 25 SX CMT ON TOP OF PLUG. 1ST PLUG AT 2400' WITH 25 SX CMT. 2ND PLUG AT 1537' WITH 80 SX CMT. 3RD PLUG AT 550' WITH 60 SX CMT. 4TH PLUG AT 64' WITH 20 SX CMT.**

Perfs:

Top	Bot	Thru	Comments
5042	5052		

KCC WICHITA
MAR 04 2014
RECEIVED

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES

Plugged through: TBG

District: 01

RECEIVED

FEB 27 2014

KCC DODGE CITY

Signed

Ken Jehlik
3/1/14

(TECHNICIAN)