

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22243-00-00
Spot: SESESESW Sec/Twnshp/Rge: 20-34S-35W
137 feet from S Section Line, 2713 feet from E Section Line
Lease Name: STALCUP A Well #: 3 SWD
County: STEVENS Total Vertical Depth: 1343 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	1230	0	WITH 210 SX CMT
SURF	5.5	762		WITH 220 SX CMT

Well Type: SWD UIC Docket No: D27371.0 Date/Time to Plug: 02/17/2014 2:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: COULDN'T PUMP INTO CASING. TAGGED TOP OF FILL AT 1050'. RUN TBG TO 1050' & FILL TO SURFACE. TOP OFF & CHECK BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2014 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL UP AT 1050'. RUN 1 1/4" TBG TO 1049' & CIRCULATE CMT TO SURFACE IN THE 2 7/8" CASING WITH 25 SX CMT. PUMP 4 SX CMT DOWN THE 2 7/8" X 5 1/2" ANNULUS TO 500#. TOP OFF 2 7/8" CASING WITH 1 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1230	1343	OH	
1028	1178		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
2/17/14

(TECHNICIAN)

RECEIVED

FEB 18 2014

KCC DODGE CITY

cc to UIC 02/20/14

KCC WICHITA

FEB 19 2014

RECEIVED

Form CP-2/3

B24