

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-22268-00-00
Spot: SESWNWNW Sec/Twnshp/Rge: 8-25S-32W
1120 feet from N Section Line, 400 feet from W Section Line
Lease Name: BROOKOVER Well #: 8-4
County: FINNEY Total Vertical Depth: 5000 feet

Operator License No.: 34904
Op Name: PALMER OIL, INC.
Address: 3118 N. CUMMINGS RD. PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1738		WITH 900 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/03/2014 5:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: KEN MCGUIRE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1950' WITH 50 SX CMT. 2ND PLUG AT 1770' WITH 50 SX CMT. 3RD PLUG AT 930' WITH 50 SX CMT. 4TH PLUG AT 450' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 02/03/2014 7:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

RAN 1" TO 150' DOWN 8 5/8" BACKSIDE. PUMPED 200 SX CMT BRINGING CMT TO SURFACE 1ST PLUG AT 1950' WITH 50 SX CMT. 2ND PLUG AT 1770' WITH 50 SX CMT. 3RD PLUG AT 930' WITH 50 SX CMT. 4TH PLUG AT 450' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 10 2014
CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Nathan Willis
2/10/14 (TECHNICIAN)

RECEIVED
FEB - 7 2014
KCC DODGE CITY

Form CP-2/3