

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-24481-00-00
Spot: NWSWNWSW Sec/Twnshp/Rge: 25-28S-19E
1960 feet from S Section Line, 150 feet from W Section Line
Lease Name: YARNELL Well #: 1(3)
County: NEOSHO Total Vertical Depth: 800 feet

Operator License No.: 32595
Op Name: MSG RESOURCES INC.
Address: 975 1400TH ST
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	800		70 SX
SURF	10	20		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2014 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MICHAEL BROWN Company: _____ Phone: (620) 365-0638

Proposed Plugging Method: Run one inch cement string inside and outside the production pipe, and cement to top

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 02/12/2014 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 1" cement string was washed down the annulus to 375'. A 1" cement string was also washed down the production pipe to 750'. The well was then pumped full of portland cement from btm to top thru the cement strings. The cement strings were removed and the well topped off with cement.

Perfs:

RECEIVED
FEB 21 2014
KCC Chanute Dist. #3

AD

KCC WICHITA

FEB 26 2014

RECEIVED

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
2/10/14
(TECHNICIAN)