

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22885-00-00  
Spot: NESESWSW Sec/Twnshp/Rge: 5-11S-20W  
408 feet from S Section Line, 1576 feet from E Section Line  
Lease Name: KENMARK-FISCHER Well #: 3  
County: ELLIS Total Vertical Depth: 1468 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1481		200 SX
SURF	8.625	257		170 SX

Well Type: SWD UIC Docket No: D20846.0 Date/Time to Plug: 02/19/2014 1:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 185 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Perforations: 990' - 1140' CH  
PBTB-1468'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/19/2014 3:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin ran in hole with tubing to 1025'. Consolidated rigged to tubing and pumped 55 sx cement w/250 # hulls mixed in to circulate cement up 4 1/2" casing. Pulled tubing. Rigged to 4 1/2" casing and pumped 20 sx cement to pressure with 200 psi and 200 psi shut in pressure. Rigged to 8 5/8" casing and pumped 10 sx cement to pressure with 200 psi and 200 psi shut in pressure.

GPS: 39.11830 -099.56069  
457' FSL 1449' FEL  
NE SE SW SE

Perfs:

Top	Bot	Thru	Comments
990	1140		

KCC WICHITA

Remarks: CONSOLIDATED CEMENTING TICKET # 43040

FEB 28 2014

Plugged through: TBG

RECEIVED

District: 04

Signed [Signature]  
(TECHNICIAN)  
ce to UIC 3/04/14

CM

FEB 28 2014