

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-21825-00-00

Spot: NENWSWSW

Sec/Twnshp/Rge: 4-34S-10E

1053 feet from S Section Line, 4895 feet from E Section Line

Lease Name: LISTER

Well #: 5

County: CHAUTAUQUA

Total Vertical Depth: 1863 feet

Operator License No.: 30930

Op Name: PAR, INC.

Address: 2201 E WILSHIRE BLVD
OKLAHOMA CITY, OK 73111

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1863		
SURF	7	40		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/04/2013 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: THOMAS H. OAST

Company:

Phone: (918) 440-6512

Proposed Plugging Method: RUN 1" TO TD (1863'). GEL HOLE. PLACE 50' CEMENT PLUG AT TD. PLACE 50' CEMENT PLUG AT 750'. PLACE CEMENT PLUG FROM 550' TO SURFACE. CUT CASING BELOW GROUND LEVEL. RESTORE SITE.

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed: 09/04/2013 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1800' gelled hole and spotted 10 sack plug. Pulled up to 1000' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 80 sacks of cement were used to plug this well.

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

DS

Remarks: WELL WAS PLUGGED BECAUSE OPERATOR LOST LEASE.

Plugged through: TBG

District: 03

Signed

KCC WICHITA

FEB 13 2014

RECEIVED

(TECHNICIAN)