

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20367-00-01  
Spot: SWSWNE Sec/Twnshp/Rge: 25-21S-35W  
1348 feet from S Section Line, 3956 feet from E Section Line  
Lease Name: RICE Well #: 1  
County: KEARNY Total Vertical Depth: 3100 feet

Operator License No.: 32198  
Op Name: PETROSANTANDER (USA) INC.  
Address: 6363 WOODWAY DR STE350  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3100	0	WITH 350 SX CMT
SURF	8.625	574		WITH 350 SX CMT

Well Type: SWD UIC Docket No: D19510.0 Date/Time to Plug: 02/08/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Revd. from: MARK PAUDA Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: ESTABLISH INJECTION RATE ON 4 1/2". FILL 4 1/2" WITH CMT FROM 1770' TO 0' WITH 115 SX CMT & HULLS. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/10/2014 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 1770' TO 0' USING 150 SX CMT & 300# HULLS. PRESSURE TO 500#. HOLDING. TAG CMT IN 4 1/2" X 8 5/8" ANNULUS 1' BELOW THE BRADEN HEAD.

Perfs:

Top	Bot	Thru	Comments
1720	1770		

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

RECEIVED

FEB 11 2014

KCC DODGE CITY

*[Handwritten Signature]*  
ce to UIC 02/21/14

(TECHNICIAN)

KCC WICHITA

FEB 18 2014

RECEIVED

Form CP-2/3

*[Handwritten Initials]*