

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26660-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 27-12S-17W
3030 feet from S Section Line, 4465 feet from E Section Line
Lease Name: THERESA Well #: 7
County: ELLIS Total Vertical Depth: 3735 feet

Operator License No.: 5252
Op Name: R. P. NIXON OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/08/2014 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC.
Proposal Rcvd. from: GEORGE Company: SHIELDS OIL PRODUCERS INC. Phone: (785) 735-4503

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 02/08/2014 7:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @1350 w/25 sx
2nd plug @775 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed Case Morris
(TECHNICIAN)

2/11/14

KCC WICHITA

FEB 24 2014

RECEIVED

FEB 18 2014