

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25728-00-00
Spot: SWSNWSE Sec/Twnshp/Rge: 28-16S-26W
1636 feet from S Section Line, 1749 feet from E Section Line
Lease Name: HOLMES Well #: 1
County: NESS Total Vertical Depth: 4675 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	241		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/20/2014 4:30 PM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Revd. from: JEREMY STUCKY Company: MAVERICK DRILLING LLC Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 2040' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 02/20/2014 6:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2040' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

RECEIVED
FEB 21 2014
KCC DODGE CITY

Signed Eric MacLaren
3/10/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

FEB 27 2014

RECEIVED