

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-27604-00-00  
Spot: SENESEW Sec/Twnshp/Rge: 14-28S-18E  
2070 feet from S Section Line, 2378 feet from W Section Line  
Lease Name: BAILEY, MARION L Well #: 14-3  
County: NEOSHO Total Vertical Depth: 931 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	924		115 SX
SURF	8.625	22		5 SX
T1	2.375	851		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/28/2013 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT AND TOP WELL OF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 08/28/2013 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to 920'. The well was then pumped full of cement from btm to top thru the cement string. The cement string was removed and the well topped off with cement. A total of 147 sacks of portland cement were used.

Perfs:

Top	Bot	Thru	Comments
786	790		
742	748		

RECEIVED  
FEB 04 2014  
KCC Chanute Dist. #3

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
3/11/14 (TECHNICIAN)

KCC WICHITA  
FEB 12 2014  
RECEIVED