

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-29607-00-00  
Spot: SENWNWSE Sec/Twnshp/Rge: 32-26S-19E  
2158 feet from S Section Line, 1982 feet from E Section Line  
Lease Name: BEEMAN, KEITH R. Well #: 32-1  
County: ALLEN Total Vertical Depth: 1085 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1073		172 SX
SURF	8.625	22		5 SX
T1	2.375	750		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/16/2013 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: LARRY GRAHAM Company: \_\_\_\_\_ Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT AND TOP OFF WITH CEMENT

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 07/16/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2 3/8" pipe to TD. Circulated cemeent through the 2 3/8" pipe from TD to surface. Pulled the 2 3/8" pipe out of the well. Topped the well off with cement. A total of 124 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
715	717		
685	688		
664	666		
593	597		
581	585		

RECEIVED

FEB 13 2014

KCC Chanute Dist. #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed

  
3/11/14 (TECHNICIAN)

KCC WICHITA

FEB 18 2014

RECEIVED

Form CP-2/3