

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-28110-00-00
Spot: NWNWSWNE Sec/Twnshp/Rge: 27-28S-17E
1355 feet from N Section Line, 2360 feet from E Section Line
Lease Name: BOLLIG, ANTHONY J Well #: 27-3
County: WILSON Total Vertical Depth: 1055 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0	0	SX
SURF	8.625	24	5	SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/25/2013 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TOTAL DEPTH THEN CEMENT TO SURFACE

Plugging Proposal Received By: ALAN DUNNING Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2013 3:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to 1010'. The wellbore was gelled and then a 50' cement plug was spotted at TD. The cement string was pulled to 500' and another 50' cement plug spotted. The cement string was pulled to 200' and the well pumped full of cement to surface. A total of 172 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
FEB 10 2014
KCC Chanute Dist. #3

AD

Remarks:

Plugged through: OH

District: 03

Signed Alan Dunning
3/11/14 (TECHNICIAN)

KCC WICHITA

FEB 12 2014

RECEIVED