

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-27205-00-00
Spot: SWNESENV Sec/Twnshp/Rge: 6-28S-20E
1970 feet from N Section Line, 1981 feet from W Section Line
Lease Name: DANIELS, CURTIS Well #: 2-6
County: NEOSHO Total Vertical Depth: 994 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	986		135 SX
SURF	8.625	21		5 SX
T1	2.375	900		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 09/04/2013 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE THEN PULL TUBING OUT AND TOP WELL OFF W/ CEMENT

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 09/04/2013 3:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was lowered to 980'. The well was then pumped full of cement from btm to top thru the cement string. The cement string was pulled and the well topped off with cement. A total of 91 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
700	702		
609	611		
578	581		
551	553		
472	476		
461	465		

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: CSG

District: 03

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

Alan Dunning
2/11/14 (TECHNICIAN)