

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-26844-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 31-27S-20E  
1974 feet from S Section Line, 1982 feet from W Section Line  
Lease Name: FINLEY, AMOS D. Well #: 31-1  
County: NEOSHO Total Vertical Depth: 1006 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	990		144 SX
SURF	8.625	22		5 SX
T1	2.375	932		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/03/2013 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, CEMENT THROUGH TUBING TO SURFACE PULL TUBING OUT AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 09/03/2013 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to 985'. The well was then pumped full of cement from btm to top thru the cement string. The cement string was pulled and the well topped off with cement. A total of 91 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
893	896		
840	842		
835	837		
766	768		
737	739		
633	635		
602	605		
497	501		
486	490		

RECEIVED

FEB 10 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning  
3/11/14  
(TECHNICIAN)

KCC WICHITA

FEB 12 2014

RECEIVED