

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-27303-00-00
Spot: W2E2SENE Sec/Twnshp/Rge: 6-28S-20E
1980 feet from N Section Line, 600 feet from E Section Line
Lease Name: HAMMANS, ARDEN A. Well #: 6-1
County: NEOSHO Total Vertical Depth: 915 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	865		115 SX
SURF	8.625	22		5 SX
T1	2.375	855		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 09/17/2013 9:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, CEMENT THROUGHG TUBING TO SURFACE PULL TUBING OUT AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 09/17/2013 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to TD. The well was then pumped full of cement from btm to top thru the cement string. The cement string was pulled and the well topped off with portland cement. A total of 100 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
813	815		
775	777		
761	763		
756	758		
686	688		
661	663		
611	613		
424	428		
412	416		

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: CSG

District: 03

KCC WICHITA
FEB 13 2014
RECEIVED

Signed

Alan Dunning
3/11/14 (TECHNICIAN)