

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-27664-00-00
Spot: NESEWNNE Sec/Twnshp/Rge: 30-30S-18E
975 feet from N Section Line, 1510 feet from E Section Line
Lease Name: LECK, DORIS Well #: 30-14
County: NEOSHO Total Vertical Depth: 982 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	8.625	20		4 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/23/2013 3:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE THEN TOP WELL OFF.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 07/23/2013 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to 980'. The wellbore was then gelled. A 50' cement plug was spotted at TD. The cement string was pulled to 500' and a 50' cement plug spotted. The cement string was pulled to 250' and the well pumped full of cement to surface. The cement string was removed and the well topped off with cement. A total of 147 sacks of portland cement were used to plug well.

Perfs:

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: OH

District: 03

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

Alan M. Dunning
3/11/14 (TECHNICIAN)