

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-28094-00-00  
Spot: SWNESENW Sec/Twnshp/Rge: 9-28S-17E  
1860 feet from N Section Line, 2225 feet from W Section Line  
Lease Name: MCMILLEN, BETTY J Well #: 9-4  
County: WILSON Total Vertical Depth: 1125 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 5.5   | 1118       |             | 165 SX  |
| SURF   | 8.625 | 198        |             | 40 SX   |
| T1     | 1.5   | 1050       |             |         |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/29/2013 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT PRO Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT THEN TOP WELL OFF W/ CEMENT

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/29/2013 12:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to 1110'. The well was then pumped full of cement from btm to top thru the cement string. The cement string was removed and the well topped off with cement. A total of 147 sacks of portland cement were used to plug well.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 903 | 909 |      |          |

RECEIVED  
FEB 11 2014  
KCC Chanute Dist #3  
AD

Remarks:

Plugged through: CSG

District: 03

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

Alan Dunning  
3/11/14  
(TECHNICIAN)