

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-27660-00-00  
Spot: SWNENWSE Sec/Twnshp/Rge: 10-28S-19E  
2165 feet from S Section Line, 1935 feet from E Section Line  
Lease Name: MIH, MARIAM L Well #: 10-11  
County: NEOSHO Total Vertical Depth: 832 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE.  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	21		5 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/03/2013 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE Phone: (620) 431-9212

Proposed Plugging Method: Spot cement plugs at TD, 500' and 300' to surface.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 06/03/2013 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was washed down to 832'. A 50' cement plug was then spotted. The cement string was pulled to 500' and a 50' cement plug spotted. The cement string was pulled to 300' and cement pumped to surface; gel spacers between. A total of 126 sacks of portland cement were used to plug well.

Perfs:

RECEIVED  
FEB 06 2014  
KCC Chanute Dist. #3

AD

Remarks:

Plugged through: OH

District: 03

Signed Alan Dunning  
3/10/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

FEB 12 2014

RECEIVED