

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-28116-00-00
Spot: SESWSNW Sec/Twnshp/Rge: 2-28S-16E
2625 feet from N Section Line, 1950 feet from W Section Line
Lease Name: OLSON, RUBY A Well #: 2-7
County: WILSON Total Vertical Depth: 1205 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	8.625	21		5 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/25/2013 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, PUMP CEMENT THROUGH TUBING, PULL TUBING OUT OF HOLE THEN TOP OFF WITH CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 04/25/2013 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 2.375" cement string was lowered to TD. The wellbore was then gelled. A 50' cement plug was spotted at TD. The cement string was pulled to 500' and another 50' cement plug spotted. The cement string was raised to 200' and the well pumped full of cement to surface. The operator reported that 168 sacks of portland cement were used to plug well.

RECEIVED
FEB 11 2014
KCC Chanute Dist. #3
AD

Remarks:

Plugged through: OH

District: 03

KCC WICHITA
FEB 13 2014
RECEIVED

Signed Alan M. Dunning
3/11/14 (TECHNICIAN)