

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-27676-00-00
Spot: SENENWNE Sec/Twnshp/Rge: 33-27S-19E
525 feet from N Section Line, 1325 feet from E Section Line
Lease Name: REINHARDT, RICHARD R Well #: 33-4
County: NEOSHO Total Vertical Depth: 782 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0	0	SX
SURF	8.625	20	5	SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/22/2013 1:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT PRO Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE THEN TOP WELL OFF WITH CEMENT.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 07/22/2013 4:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to 782' and a 50' cement plug spotted. The cement string was pulled to 500' and another 50' cement plug spotted. The cement string was pulled to 250' and cement pumped to surface; gel spacers between. The cement string was removed and the well topped off. A total of 126 sacks of portland cement were used to plug well.

Perfs:

RECEIVED

FEB 06 2014

Chanute Dist. #3

AD

Remarks:

Plugged through: OH

District: 03

Signed

Alan Dunning
3/22/14
(TECHNICIAN)

KCC WICHITA

FEB 12 2014

RECEIVED