

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-27179-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 31-27S-20E
1981 feet from N Section Line, 993 feet from E Section Line
Lease Name: ROBERTS, MAX D. Well #: 31-1
County: NEOSHO Total Vertical Depth: 1035 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1018		135 SX
SURF	8.625	22		5 SX
T1	2.375	956		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 09/04/2013 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, CEMENT THROUGH TUBING TO SURFACE PULL TUBING OUT AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2013 3:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was lowered to 1010'. The well was then pumped full of cement from btm to top thru the cement string. The cement string was pulled and the well topped off with cement. A total of 98 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
914	916		
858	860		
852	854		
756	758		
651	653		
618	621		
511	515		
500	504		

RECEIVED
FEB 10 2014
KCC Chanute Dist. #3
AD

Remarks:
Plugged through: CSG

District: 03

Signed Alan M. Dunning
3/11/14 (TECHNICIAN)

KCC WICHITA
FEB 12 2014
RECEIVED