

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-28177-00-00  
Spot: SWSENWSE Sec/Twnshp/Rge: 24-29S-15E  
1475 feet from S Section Line, 1845 feet from E Section Line  
Lease Name: SHORT, STERLING Well #: 24-6  
County: WILSON Total Vertical Depth: 1025 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	8.625	22		5 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2013 11:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, PUMP CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 07/24/2013 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was washed to 1025'. The wellbore was then gelled. A 50' cement plug was spotted at TD. The cement string was pulled to 500' and another 50' cement plug was spotted. The cement string was raised to 250' and the well pumped full of cement. The operator reported that 112 sacks of portland cement were used to plug well.

Perfs:

RECEIVED

FEB 11 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: OH

District: 03

KCC WICHITA

FEB 13 2014

RECEIVED

Signed

Alan Dunning  
3/11/14  
(TECHNICIAN)