

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-26228-00-00  
Spot: E2W2NESE Sec/Twnshp/Rge: 6-29S-19E  
1980 feet from S Section Line, 800 feet from E Section Line  
Lease Name: TRIPLETT, C.W. Well #: 6-1  
County: NEOSHO Total Vertical Depth: 983 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE,  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	980		123 SX
SURF	8.625	22		4 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2013 8:00 AM  
Plug Co. License No.: 34453 Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION  
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT PRO Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT THEN TOP WELL OFF WITH CEMENT

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 06/24/2013 5:00 PM KCC Agent: ALAN DUNNING

**Actual Plugging Report:**

A 2.375" cement string was run to 980'. The well was then pumped full of cement from btm to top thru the cement string. The cement string was pulled and the well topped off with cement. The wellhead was then hooked onto and the well pressured to 500 psi which held. A total of 156 sacks of portland cement were used to plug well.

**Perfs:**

Top	Bot	Thru	Comments
929	933		
877	878		
871	873		

RECEIVED

FEB 06 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning

(TECHNICIAN)

KCC WICHITA

FEB 12 2014

RECEIVED