

~~OK TO INV.~~ AS PLUS DT'S. W/IN 5 YR.

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-01087-00-00 BILLING CUTOFF.
Spot: NESWNENE Sec/Twnshp/Rge: 16-29S-16E
839 feet from N Section Line, 795 feet from E Section Line
Lease Name: WASSON, FLOYD 16-29-16 Well #: OW1
County: WILSON Total Vertical Depth: 800 feet

Operator License No.: 33343

Op Name: POSTROCK MIDCONTINENT PRODUC

Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	0	0		0 SX

Well Type: OG

UIC Docket No:

Date/Time to Plug: 09/10/2012 8:00 AM

Plug Co. License No.: 34453

Plug Co. Name: POSTROCK ENERGY SERVICES CORPORATION

Proposal Rcvd. from: LARRY GRAHAM

Company: POSTROCK MIDCONTINENT

Phone: (620) 432-4200

Proposed
Plugging
Method:

WASH TO TD THROUGH TUBING, CEMENT THROUGH TUBING UNTIL CEMENT RETURNS TO SURFACE,
TRIP TUBING OUT OF HOLE THEN TOP WELL OFF WITH CEMENT.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: PARTIAL

Date/Time Plugging Completed: 09/11/2012 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1" cement string was washed down to 600'. 175 sacks of portland cement were then pumped. The cement string was removed and the well will be topped off tomorrow. 9-11-2012: A cement string was lowered to 130'. The well was then pumped full of cement. A total of 317 sacks of portland cement were used.

RECEIVED

JAN 31 2014

KCC Chanute Dist. #3

AD

Remarks: THIS IS AN OLD WELL THAT BROKE OUT DURING THE PRESSURE TREATMENT OF A NEARBY WELL.

Plugged through: OH

District: 03

Signed

Alan M. Dunning

(TECHNICIAN)

3/11/14

KCC WICHITA

FEB 06 2014

RECEIVED