

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-133-26832-00-00
Spot: NWSESW Sec/Twnshp/Rge: 9-27S-19E
658 feet from S Section Line, 704 feet from W Section Line
Lease Name: WEESE, LEROY K. Well #: 9-1
County: NEOSHO Total Vertical Depth: 1083 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1071		120 SX
SURF	8.625	21		5 SX
T1	2.375	966		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 07/17/2013 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: LARRY GRAHAM Company: POSTROCK MIDCONTINENT PRO Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT AND TOP OFF WITH CEMENT

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 07/17/2013 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375" cement string was run to 1083'. The well was then pumped full of cement from btm to top. The cement string was removed and the well topped of with cement. A total of 93 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
940	944		
930	934		
814	816		
703	705		
670	673		
649	651		
567	571		
557	561		

RECEIVED

FEB 06 2014

KCC Chanute Dist. #3

AD

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
3/11/14
(TECHNICIAN)

KCC WICHITA

FEB 12 2014

RECEIVED

Form CP-2/3