



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 24 1967
 11-26-67
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Nov. 18, 1967.

Dear Sir:

Mr. Don Rider of K & E Drilling Oil Co. has this date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling Oil Co.

Complete Address: 719 Union Center Wichita Kansas.

Lease Name: Schupdach A Well No. #1

Location: C-NW-NE-SE Sec. 12 Twp. 34S Rge. 12W (E) (W) W

County Barber Total Depth 4700 ft. Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

250 ft. of 8 5/8" surface pipe circulated with cement.
Mud to 250 ft. plug, 1/2 sack hulls & 25 sacks cement. Mud
to 40 ft. plug, 1/2 sack hulls & 10 sacks cement to base of cellar.
2 sacks cement in rathole.

Very truly yours,

Harman Gustafson
 Conservation Division Agent