

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 4 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. T. F. Brown of Gabbert-Jones, Inc. has this  
date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Falcon Seaboard Drilling Company

Complete Address: 3801 South Bryan, Oklahoma City, Oklahoma

Lease Name: Wilford Betzer Well No. # 1

Location: 1200' SNL & 2310' EWL Sec. 11 Twp. 31 Rge. 17 (E)(W) W

County Comanche Total Depth 5090' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Brown was instructed to plug the well as follows:

450' of 8 5/8" surface pipe, cement circulated with 375 sacks.

Fill hole with drilling mud to 300', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', bridge with hulls, and cement with 10 sacks to base of

the cellar. Bridge and cement rat and mouse hole with 4 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent