

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Nov. 2, 1967

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1967
11-15-67
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply. has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Santa Fe Pipe & Supply

Complete Address: Box 562 Great Bend, Kansas.

Lease Name: V. J. Cook Well No. #1

Location: SE-NW-NW Sec. 18 Twp. 34 Rge. 12W (E)(W) W

County Barber Total Depth 4900' Oil Well

Gas Well x Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

~~272 ft. of surface pipe. 4899 ft. of 5 1/2" long string
Plug at 4861 ft. Top perforation at 4821 ft. Sand to 4800'
and 5 sacks cement. Mud to 250 ft., 10 ft. rock bridge &
25 sacks cement. Mud to 40 ft. & 10' rock bridge. 10 sacks
cement to surface. 3427 ft. long string (5 1/2" pipe) pulled.~~

Very truly yours,

Herman Justus
Conservation Division Agent